



METRO RAIL CORPORATION LIMITED
(A Joint Venture of Govt. of India and Govt. of Karnataka)
BMTC Complex, 3rd floor, Shanthinagar,
K.H. Road, Bangalore-560027.

Ph: 080-22969300, 22969301 Fax:
22969222

E-mail: bmrcl@dataone.in
Web:www.bmrc.co.in

No.BMRCL/Quotation/GIS Building/2012-13/ 18468 Date:21.03.2013

SHORT TERM QUOTATION FOR BASEMENT EXCAVATION AT GIS MYSORE ROAD

Bangalore Metro Rail Corporation Ltd.,(BMRCL) a Joint Venture of Government of Karnataka and Government of India, Limited invites sealed Quotations from eligible agencies for basement excavation for GIS Building for BMRCL/KPTCL Sub - Station at Mysore Road in Reach-2.

Details of Quotation are as under:

Sl. No	Name of the Work	Approximate Amount of work in Rs.	EMD in Rs.	Period of completion
1.	Earth work excavation in ordinary soil/ hard soil and in ordinary rock/ hard rock by Chemical splitting and excavation by using Excavator mounted with Hydraulic breaker including disposal of excavated material.	19.00 Lakhs	Rs 19,000.00	30 days

Completion Period: -30 days from the date of issue of work order.

I. Eligibility Criteria for Bidders:

- 1) The Bidder should have a valid **class-2 and above** Civil contract license. Notarized copy of the License shall be furnished. Original Document of the license shall be produced for verification by BMRCL after opening of the quotation as requested.
- 2) The bidder should have similar experience of work as mentioned above and should have completed similar works.
- 3) The Bidder shall furnish copies of audited and certified financial reports in support of the same, for the financial years 2009-10, 2010-11 and 2011-12.
- 4) The Bidder should not have been black listed by any government department. The Bidder should furnish a declaration to that effect.

II. Terms and Conditions

1. The bidder has to quote the offer on percentage basis for items in section-A of schedule and own rate for items in section-B of schedule.
2. Rates to be quoted inclusive of all taxes and other statutory levies as applicable.
3. Each bidder must submit only one quotation.
4. Self attested copies of License, VAT Registration and IT PAN should be enclosed with the quotation.
5. No blasting of any kind will be permitted including controlled blasting.
6. The selection of the bidder will be on the basis of overall lowest amount.

III. Conditions for Award of Contract.


1. The contract shall be awarded to the bidder whose quotation is considered to be substantially responsive and who has offered the lowest amount.
2. Notwithstanding the above, the Company reserves the right to accept or reject any quotation or to cancel the bidding process and reject all quotations at any time prior to the award of contract, without assigning any reasons there for.
3. The quantities indicated in the Schedule are approximate.
4. The successful bidder shall enter into a formal agreement with the company on a stamp paper of Rupees 100.00 with usual terms and conditions for civil works and specifications.

Blank quotation forms can be downloaded from the Company website www.bmrc.co.in or can be obtained from the office of the Chief Engineer (Reach-2), Bangalore Metro Rail Corporation Ltd, 3rd floor, BMTC Complex, Shanthinagar, Bangalore-560027 at free of cost.

The quotation should be super scribed "QUOTATION FOR BASEMENT EXCAVATION for GIS Building for BMRCL/KPTCL Sub - Station at Mysore Road in Reach-2".

The last date of receipt quotations is 30-03-2013 up to 3 PM. The quotations will be opened on 30-03-2013 at 3.30 PM at BMRCL head office and the bidder may depute his authorize representative to be present at time of opening of the quotations.

For further clarification if any, the bidder may contact the under signed on any working day. Sealed quotations should be addressed to the Chief Engineer (Reach-2), Bangalore Metro Rail Corporation Ltd, 3rd floor, BMTC Complex , Shanthinagar, Bangalore-560027.



(D.M. Ramtekkar)

Chief Engineer (R2) BMRCL

Schedule

Client : Bangalore Metro Corporation Limited,(BMRCL), Bangalore

General Consultnt : RITES-OCCL-PBI-SYSTRA

Name of work : Earth work excavation for GIS sub Station at Mysore Road in reach-2.

Item No.	Item Description	Unit	Qty	Rate in Rs	Total Amount in Rs
Section-A					
1	Earth work excavation for Basement / foundation of GIS buildings, in ordinary soil up to 2.00m depth and stacking the excavated soil clear from edges of excavation with lead upto 50mtr. after breaking of clods complete as per specifications and approved drawings and as directed by Engineer- in chagre.	CUM	250	132.50	33125.00
2	Earth work excavation for Basement/foundation of GIS Building in Hard soil or Murrum up to 2.00m depth including dressing the bottom and sides of pites and trenches and stacking the excavated soil clear from edges of excavation with lead upto 50mtr after breaking of clods complete as directed by Engineer- in charge.	CUM	350	198.22	69377.00
3	Removal and Disposal of excavated stuff / unserviceable soil including excavated rock to the dumping area including all lead and lift specified by BBMP or as directed by Engineer- in charge.	CUM	1100	133.70	147070.00
Section -A total Amount in Indian Rupees					249572.00
Bidder quoted percentage Above or Below or at Par on the amount indicated in Section A.		_____ % Above/ Below/At Par			

Section-B						
Item No.	Item Description	Unit	Qty	Quoted Rate in Rs	Amount in Rs	Amount in words
4	Earth work excavation for Basement/foundation of GIS building as per the drawing in ordinary rock/DIR by in hard rock by Chemical splitting and excavation by using Excavator mounted with Hydraulic breaker not exceeding 0 to 2.0Mtr in depth including dressing the bottom and sides of pits and trenches, stacking the excavated rock with required lift up to 2 m, clear from edges of excavation with lead upto 50mtr including cost of labour, machinaries, consumables etc complete and as per instruction of Engineer in charge.	CUM	350			
5	Earth work excavation for Basement / foundation of GIS building as per the drawing in hard rock by Chemical splitting and excavation by using Excavator mounted with Hydraulic breaker not exceeding 0 to 2.0Mtr in depth including dressing the bottom and sides of pites and trenches, stacking the excavated rock with required lift up to 2 m, clear from edges of excavation with lead upto 50mtr including cost of labour, machinaries, consumables etc complete and as per instruction of Engineer in charge.	CUM	150			
Section -B total Amount in Indian Rupees						
Bidder has to quote the rate for item no: 4 & 5 and total amount in figure and words						
Grand total (A+B) Amount in Indian Rupees						